CHITALDRUG DIVISION.

Dated 24th October 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 20th November 1906, for constructing a 3rd class travellers' bungalow at Hosdurga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1908.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory Notes, as earnest money, and be superscribed "Tender for constructing a 3rd class travellers' bungalow at Hosdurga," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for constructing a 3rd class travellers' bungalow at Hosdurga (with] steel roof):—

	Items of work.	Per	Quantity.
1	Earthwork, excavation	C. yd.	217
2	Burnt stone in chunam	C. ft.	6,159
3	Burnt brick in chunam	,,	5098
4	Burnt brick in chunam (arch work)	,,	50
5	Burnt stone slabs	S. ft	683
6	Plastering with chunam	Sqr.	38·20
7	Do do rough	,,	41·72
8	Pointing with chunam	Sqr.	5·15
9	White and color washing	,,	85·07
10	Flooring with Mangalore tiles over 3" concrete, etc. ...	,,	6·02
11	Flooring with Cuddapah slabs do ...	,,	5·03
12	Roofing with 1st class Mangalore tiles excluding teak reepers	,,	34·43
13	Ridge tiles set in mortar	Rft.	159
14	Ventilating tiles	Each	12
15	Steel works	Cwt.	92½
16	Teakwood doors panelled	S. ft.	224
17	Do windows outside pannelled inside glazed with iron bars, etc., complete	S. ft.	70
18	Teakwood battened doors	S. ft.	111
19	Do do windows, outside battened shutters, inside glazed shutters with iron bars ...	,,	9
20	Teakwood battened windows with iron bars ...	,,	8
21	Do do ventilators glazed ...	,,	4
22	Cut stone pillars with capitals, etc.	Each	6
23	Ornamental eave-board, 9" depth, 1" thick ...	Rft.	161
24	Painting doors and windows and eave-boards ...	Sqr.	12·69
25	Clearing site, levelling ground and fencing ...	L. S.	..
26	Flooring with gravel	Sqr.	4·89
27	Cornice work at gable ends	Rft.	76
28	Stone flagging with cement pointing	Sqr.	1·20
29	Sinking a new well	L. S.	...
30	Constructing a latrine	,,	...

K. PRAHLADA RAO,
Exec. Engineer.